

Safe Routes to Schools Task Force  
Update on Current B/P Projects

	School/s	Description/Location	Funding Source	Projected Cost	Schedule	Remarks
1	Mill Valley Middle, Tam High	Pedestrian & bicycle improvements (Miller Ave)	TAM Regional Tranportation Grant/ Other funding TBD	6,000,000.00	2017	Funding: Measure A, SR2S cycle 10, HSIP cycle 5 Status: project is under construction and expected to be completed at the end of 2017
2	Mill Valley Middle, Tamalpais High	Bike lanes and signal hardware upgrades along Camino Alto between Miller and E. Blithedale.	HSIP Cycle 6	396,000.00	2016-2017	Scope of work: This project involves the construction of Class II bike lanes along Camino Alto between Miller Ave and E. Blithedale, as well as improvements to the signalized intersections including 12" traffic signal heads, LED lights, visors, accessible pedestrian push buttons, and optical bicycle detectors. Status: under design and construction expected summer 2017.
3	Old Mill School	Sidewalk gap closure on Throckmorton Ave	Measure A, Safe Pathways	25,000.00	2016	Scope of Work: Sidewalk gap closure of approximately 270 linear feet on the south side of Throckmorton Ave between Laurel Street and Josephine Street - 0.13 miles west of old mill school. Status: designed completed and construction expected by the end of 2016.
4	Mill Valley Middle, Tamalpais High	Improvements on Camino Alto between Miller and Sycamore; Improvements to intersection Camino Alto/Sycamore	Measure A, Safe Pathways	480,000.00	2016-2017	Scope of work: <ul style="list-style-type: none"> <li>• Widening approximately 120 LF of roadway just north of the Camino Alto /Sycamore Avenue intersection to accommodate future Class II bike lanes.</li> <li>• Install bicycle detection cameras or loops at the 3 main traffic signals on Camino Alto between Miller Avenue and E. Blithedale Avenue.</li> <li>• Install accessible curb ramps, realign existing crosswalks, and widen south east corner at the intersection of Camino Alto/Sycamore Avenue.</li> <li>• Widening of existing multi-use path on east side of Camino Alto between Miller Avenue and Sycamore Avenue.</li> </ul> Status: Under design and construction expected summer of 2017
5	Edna Mcguire	Feasibility study to SLP 318 - Lomita/Ashford to MV-Sausaliton MUP	Local	25,000.00	2016-2017	Status: Study of a connection path will start in 2016. Project approved by Council in August 2016.
6	Old Mill School	Reconstruction of SLP 230 (Gardner Steps)	Local	90,000.00	2016-2017	Scope of work: Replace existing stair with concrete stairs and railing on both sides. Status: Design has been completed. Council to approve design in October 2016 and construction to start in January/February 2017.